

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21640-00-00 # 151.13
Spot: NWSWNESW Sec/Twnshp/Rge: 35-21S-23W
1976 feet from S Section Line, 1565 feet from W Section Line
Lease Name: CHRISTIE Well #: 1-35
County: HODGEMAN Total Vertical Depth: 4650 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	290		WITH 220 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/15/2010 10:00 PM
Plug Co. License No.: 34317 Plug Co. Name: BEREDCO LLC
Proposal Rcvd. from: MARK LEIKER Company: BEREDCO LLC Phone: (316) 265-3311

Proposed Plugging Method: 1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 80 SX CMT. 3RD PLUG AT 280' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 05/16/2010 12:00 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 80 SX CMT. 3RD PLUG AT 320' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED

MAY 21 2010

KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 28 2010

CONSERVATION DIVISION
WICHITA, KS

Form SP-24