

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-20061-00-00  
Spot: NWNESW Sec/Twnshp/Rge: 32-16S-19W \$124.80  
2310 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: OHNMACHT Well #: 6  
County: RUSH Total Vertical Depth: 3840 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	269		WITH 175 SX CMT
DVT		1375		CMT TO SURFACE
PROD	4.5	3815	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/04/2010 2:15 PM  
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC  
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO LLC Phone: (785) 628-6101

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/04/2010 5:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

1ST PLUG CLEAN OUT CASING TO 3795'. PUMP 15 SX GEL -200# HULLS & 40 SX CMT. 2ND PLUG PULL TBG TO 1400'. CIRCULATE CMT TO SURFACE WITH 160 SX CMT. 3RD PLUG PUMP DOWN 4 1/2" X 8 5/8" ANNULUS WITH 10 SX CMT. 4TH PLUG TOPPED OFF CASING WITH 30 SX CMT.

Perfs:

6/01/10  
2010061164

RECEIVED  
MAY 24 2010  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Jerry W Stapleton  
PWR-TT (TECHNICIAN)

RECEIVED  
MAY 18 2010  
KCC DODGE CITY

Form CP 3/3