

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01392-00-01
Spot: SENWSW Sec/Twnshp/Rge: 16-9S-21W *121-*
1650 feet from S Section Line, 4290 feet from E Section Line
Lease Name: ANDRESON Well #: A6
County: GRAHAM Total Vertical Depth: 3723 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10	130	0	125 SX
T1	2.875	3690		
L1	4.5	3723	0	125 SX
PC		1483		250 SX COM CMT
PROD	5.5	3712	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/18/2010 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: KENNETH VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered 290 sxs 60/40 pozmix - 4% gel - 200# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/18/2010 9:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 4 1/2" casing - pumped 280 sxs 60/40 pozmix - 4% gel with 200# hulls.
S.I.P. 300#.
Visually checked annulus - cement to surface.

Perfs:

Top	Bot	Thru	Comments
3414	3599		LANSING
1700	2000		

6/02/10
2010061165

RECEIVED
MAY 24 2010

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #41691.

Plugged through: CSG

District: 04

Signed Pat Bedore
(TECHNICIAN)

CM

MAY 19 2010

BARNETT OIL COMPANY

#6

ANDRESON A

16-9-21W
SE NW SW

Contr. BARNETT DRILLING, INC.

GRAHAM

County

E 2225

Comm. 8-9-48

Comp. 9-10-48

IP 3000 BOPD
DRAW DOWN

Tops	Depth	Datum
LANS	3468	-1243
ARB	3711	-1486
T.D.	3725	-1500

8" 138
5" 3712

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS