

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-21105-00-01  
Spot: NWNWSW Sec/Twnshp/Rge: 34-29S-34W  
1989 feet from S Section Line, 330 feet from W Section Line  
Lease Name: MLP CLAWSON Well #: 3-34  
County: HASKELL Total Vertical Depth: 5700 feet

\$ 185.25

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: 6200 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1775		WITH 2 SX CMT
CIBP		5510		WITH 1 SX CMT
SURF	8.625	1765		WITH 650 SX CMT
L1	4.5	5385	1516	WITH 150 SX CMT
PC		3013		WITH 350 SX CMT
PROD	5.5	5699	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/18/2010 1:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: STEVE EMICH Company: CHESAPEAKE Phone: (620) 277-0803

Proposed Plugging Method: PLUGGING PROPOSAL SAME ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/18/2010 4:30 PM KCC Agent: JACK MACLASKEY

**Actual Plugging Report:**

CIBP @ 5510' WITH 1 SX CMT. CMT RETAINER @ 5100' WITH 190 SX CMT PUMPED THROUGH RETAINER. CIBP @ 1775' WITH 2 SX CMT. CUT 5 1/2" @ 833'. COULDN'T PULL. PERFORATE 5 1/2" @ 675' & CIRCULATED 150 SX CMT TO SURFACE. 5 1/2" & 5 1/2" X 8 5/8" ANNULUS FULL.

**Perfs:**

Top	Bot	Thru	Comments
5531	5536		ST. GENEVIEVE
5448	5462		CHESTER
5432	5444		CHESTER

6/02/10  
2010061167

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 28 2010

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED  
MAY 21 2010  
KCC DODGE CITY

Signed Jack MacLaskey  
(TECHNICIAN)