

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-00482-00-00

139.10

Spot: NESESE

Sec/Twnshp/Rge: 1-25S-14W

990 feet from S Section Line,

330 feet from E Section Line

Lease Name: SEEVERS LKC UT

Well #: 8-1

County: STAFFORD

Total Vertical Depth: 4280 feet

Operator License No.: 32334

Op Name: CHESAPEAKE OPERATING, INC.

Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1887		WITH 2 SX CMT
CIBP		3910		
SURF	8.625	274		WITH 250 SX CMT
PROD	5.5	4276	1300	WITH 200 SX CMT

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/25/2010 9:00 AM

Plug Co. License No.: 5105

Plug Co. Name: CLARKE CORPORATION

Proposal Rcvd. from: KEITH SHAHAN

Company: CHESAPEAKE OPERATING

Phone: (620) 277-0803

Proposed Plugging Method: SET CIBP @ 3600' WITH 2 SX CMT. PLUG AT 860' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: NONE

Date/Time Plugging Completed: 05/25/2010 11:00 AM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

TBG STUCK IN HOLE. SHOT TBG @ 3325' & ATTEMPTED TO PULL WITH NO SUCCESS. FREE POINTED TBG @ 1930'. SHOT & RECOVERED TBG AT 1900'. SET CIBP @ 1887' WITH 2 SX CMT. 1ST PLUG AT 1300' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 860' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4276	4280		
3644	3904		

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 01 2010

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

6/02/10
2010061167

District: 01

RECEIVED

MAY 27 2010

KCC DODGE CITY

Signed

Richard M. Lacey

(TECHNICIAN)