

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-27300-00-01 * 44.69
Spot: NWSWSW Sec/Twnshp/Rge: 22-23S-18E
705 feet from S Section Line, 4890 feet from E Section Line
Lease Name: KEOWN Well #: 2 W
County: ALLEN Total Vertical Depth: 1375 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF		20		

Well Type: SWD UIC Docket No: D26142.0 Date/Time to Plug: 03/18/2010 10:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: BUTCH Company: COLT ENERGY Phone: (620) 365-3111

Proposed Plugging Method: RUN PIPE TO TD, CIRCULATE PORTLAND CEMENT TO SURFACE.

Plugging Proposal Received By: JOHN ALMOND Witness Type: NONE
Date/Time Plugging Completed: 04/13/2010 12:00 AM KCC Agent: JOHN ALMOND

Actual Plugging Report:

COMPANY PULLING UNIT RAN 1" PIPE TO 1375', ESTABLISHED CIRCULATION, PUMPED 50 SACKS PORTLAND CEMENT, PULLED 1" PIPE TO 950', PUMPED 50 SACKS PORTLAND CEMENT, PULLED 1" PIPE TO 500', PUMPED 40 SACKS PORTLAND CEMENT TO SURFACE, PULLED 1" PIPE OUT, TOPPED WELL OFF WITH 3 SACKS PORTLAND CEMENT, USED 143 SACKS PORTLAND CEMENT WITH 50/50 POZ MIX WITH 6% BENTONITE GEL.

Perfs:

RECEIVED

JA

KCC Chanute Dist. #3

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 28 2010

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed

John Almond
(TECHNICIAN)