

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20966-00-01
Spot: SENWSW Sec/Twnshp/Rge: 11-13S-21W # 126.04
1683 feet from S Section Line, 4289 feet from E Section Line
Lease Name: HAMBURG OWWO Well #: 4
County: TREGO Total Vertical Depth: 3878 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	241	0	w/175 sxs cmt
PROD	4.5	3900	0	w/350 sxs cmt

Well Type: EOR UIC Docket No: _____ Date/Time to Plug: 05/20/2010 11:30 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: GEORGE STOPPLEWORTH Company: DARRAH, JOHN JAY, JR. Phone: (316) 263-2243

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.
CIBP at 3634'. Tubing tagged at 2261'. DV at 1561' w/300 sxs.
Squeezed 1900' - 1919' w/400 sxs - lost circulation. *casing collapsed.*
Note: EOR Amended Application was filed 07/30/2008 - E25,700 - well was never completed. Plugged 05/21/2010.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/21/2010 4:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

05/20/2010 - Ran tubing to 2261' - pumped 350 sxs cement with 500# hulls - no return.
Shut down 45 minutes - pulled tubing to 1846' - pumped 125 sxs cement - no return -
pulled out - waited until the next day.
05/21/2010 - Tagged bottom at 1920' - pulled up to 1916' - pumped 25 sxs
60/40 pozmix - 4% gel - 3% cc.
Let set three hours - ran tubing in - tagged cement at 1620' - pumped 110 sxs cement -
good circulation of cement.
Pulled tubing out - filled 4 1/2" - pumped 15 sxs cement - full - plug complete.

Perfs:

*6/01/10
2010061171*

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 26 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT CEMENTING COMPANY-TICKET #17635 - SECOND DAY TICKET #17593.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

JOHN JAY DARRAH, JR.
405 CENTURY PLAZA
WICHITA, KS 67202

#4 HAMBURG 'OWWO'

11-13-21W
SE NW SW

CONTR UNKNOWN

CTY TREGO


GEOL

FIELD HOMBURG

ELV 2175 KB SPD 1/7/83

CARD ISSUED 6/3/82

IP P 60 BOPD & 5% WTR
LANS 3502-3650 OA



API 15-195-20,966-A

LOG	Tops	Depth/Datum
ANH		1538+ 637
B ANH		1582+ 593
TOP		3204-1029
HEEB		3429-1254
LANS		3464-1289
B KC		3708-1533
MARM		3781-1606
ARB		3858-1683
PBTD		3875-1700
TD		3878-1703

OLD INFO: OPERATOR WAS JOHN JAY DARRAH, JR., #4 HAMBURG, SPD 3/12/82, SET 8 5/8 " 241/175SX, 4 1/2 " 3900/350SX, COMPLETED AS P 22.5 BO & 7 BWPD, ARB 3862-3867 (CARD ISSUED: 6/3/82) CONTR: MALLARD DRUG., GEOL: GERALD HONAS

DST (1) 3520-3560 (LANS) / 30-30-30-30, 50' GIP, REC 10' OCM, 60' M, SIP 507-430#, FP 77-97#

DST (2) 3790-3820 (MARM) / 45-45-45-45, REC 570' SW, SIP 910-833#, FP 55-262#

DST (3) 3860-3870 (ARB) / 45-45-45-45, REC 130' DM, SIP 987-877#, FP NA

MICT - CO, PF (ARB) 10/3861-3871, AC 500G, AC DID NOT GO, SWB 1700' OB, SWB 34 BF/30", SC OIL, SQZ W/150SX, DO CMT, RE-PF (ARB) 3862-3867, AC 500G, 1 PULL 60"/3 1/2 BF, SWB 60", 2-3 BF W/SC OIL, SWB 60" 5-6 BF (50% OIL), R&T, POP, P 22.5 BOPD & 7 BWPD, 5/7/82

NEW INFO: RE-ENTERED 1/7/83, WSH DWN, MICT - CO, PF (LANS) 1/3650, 1/3630, 1/3543, 1/3509, 1/3502, AC 5000 GAL, SWB LD, R&T, POP, P 60 BOPD, 5% WTR, 1/11/83

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS