

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20655-00-00

Spot: S2NWNE Sec/Twnshp/Rge: 23-14S-15W

4290 feet from S Section Line, 2310 feet from E Section Line

Lease Name: NIEDENTHAL

Well #: 7

County: RUSSELL

Total Vertical Depth: 3240 feet

105.30

Operator License No.: 33830

Op Name: HEWITT ENERGY GROUP, INC.

Address: 15 W S TEMPLE STE 1050
SALT LAKE CITY, UT 84101

String Size Depth (ft) Pulled (ft) Comments

SURF 8.625 236 0 w/150 sxs cmt

PROD 5.5 3229 0 w/100 sxs cmt

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/17/2010 8:14 AM

Plug Co. License No.: 3004

Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.

Proposal Recd. from: AARON

Company: HEWITT ENERGY GROUP INC.

Phone: (316) 633-0469

Proposed Ordered 400 sxs 60/40 pozmix - 4% gel - 200# hulls - 10 sxs gel.

Plugging Bad spot in casing at 330'.

Method: Perfs 850' 1600'.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 05/17/2010 2:00 PM

KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Tubing at 3130' - pumped 10 sxs gel - followed with 50 sxs cement with 200# hulls.

POOH. Ran in and perfed at 1600' and 850'.

Ran tubing to 1660' - pumped 100 sxs cement.

Pulled tubing to 400' - pumped 75 sxs cement - cement circulated.

Shut in backside and pumped 75 sxs cement - fluid circulating out Braden head.

Circulation shut off.

POOH. Hooked up to Braden head and pumped 25 sxs cement - cement circulated out casing.

*6/01/10
2010061176*

RECEIVED

MAY 24 2010

KCC WICHITA

Remarks: COPELAND CEMENTING & ACID COMPANY-TICKET #37044.

Plugged through: TBG

District: 04

Signed Ray A. Dinkel

(TECHNICIAN)

CM

A. F. SCHMIDT & ASSOCIATES
BOX 662, RUSSELL, KS.
CONTR SHIELDS DRILLING CO.

#7 NEIDENHAL

23-14-15W
APP C S $\frac{1}{2}$ NW NE

GEOL

22844

E 1815 KB c3/22/74 CARD ISSUED 5/2/74

FIELD, GORHAM

FIELD, GORHAM

API 15-167-20,655

IP F 40 BUPD NW NAT
ARR 3223-25

SMP TIPS DEPTH

ARB 3223-25

8-5/8" 236/150sx, 5 $\frac{1}{2}$ " 3229/100sx

NO LOG

NO DST'S

PF /3223-25, FU 1000' OIL, NW, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS