

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01765-00-00
Spot: NENESW Sec/Twnshp/Rge: 24-10S-21W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease Name: ACHESON Well #: 4
County: GRAHAM Total Vertical Depth: 3798 feet

123,44

Operator License No.: 31822
Op Name: JOLEN OPERATING COMPANY
Address: 100 N BROADWAY AVE STE 2460
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	224	0	w/175 sxs cmt
L1	4.5	3798		275 SX
PC		1665		500 SX
PROD	5.5	3756	0	w/150 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/18/2010 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: PERRY S. HENMAN Company: JOLEN OPERATING COMPANY Phone: (785) 625-9448

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.
Port collar 1665' w/500 sxs.
4 1/2" liner 3750' to 3798'.
Sanded off to 3750'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/18/2010 12:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3640' - pumped 100 sxs cement with 225# hulls.
Pulled tubing to 2890' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 2115' - pumped 200 sxs cement - good circulation of cement.
Pulled tubing out - tied onto backside - squeezed with zero sxs cement - full.
Pumped 25 sxs down 5 1/2" - full - shut in.

Perfs:

Top	Bot	Thru	Comments
3756	3790		ARBUCKLE
3610	3635		LANSING

6/01/10
2010061179

RECEIVED
MAY 19 2010
KCC WICHITA

Remarks: SWIFT CEMENTING COMPANY-TICKET #17634.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN) CM

MAY 19 2010

ANDERSON-PRI CHARD

#1 ACHESON

24-10-21W
NE NE SW

Contr. GLENN PEEL GRAHAM County

E 2202RB Comm. 7-2-54 Comp. IP 207 BOPD, NO WTR:

Tops	Depth	Datum
ANH	1645	557
TOP	3211	=1009
HEEB	3414	=1212
TOR	3439	=1237
LANS	3455	=1253
B/KC	3677	=1475
CONG	3727	=1525
WEA SIMP	3741	=1539
ARB	3754	=1552
TD	3758	=1556

Casing

8" 224
5" 3756

DST 3607-39/1 HR, 1740' GAS
60' H O & GCM, 900' OIL

BHP 1090#:

DC: CO 3859: SWB 9 BOPH,
NO WTR/8 HRS:

WHITE POOL

+	+	+	+
+	+	+	+
+	+	+	+
+	+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS