

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20818-00-00
Spot: SWNE Sec/Twnshp/Rge: 14-34S-28W \$ 196.63
3300 feet from S Section Line, 1980 feet from E Section Line
Lease Name: DAVIS Well #: 1-14
County: MEADE Total Vertical Depth: 6050 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2942		
SURF	8.625	607		WITH 180 SX CMT
PROD	5.5	6008	2250	WITH 235 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/21/2010 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 2875' WITH 5 SX CMT. PLUG AT 1220' WITH 15 SX GEL & 50 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/21/2010 11:15 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SAND TO 2875' & 5 SX CMT. 1ST PLUG AT 1220' WITH 15 SX GEL & 50 SX CMT W/100# HULLS. 2ND PLUG PULL TO 630' & PUMP 50 SX CMT W/100# HULLS. 3RD PLUG PULL TO 40' & PUMP 35 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2925	2934		

6/02/10
2010061183

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 28 2010

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL 3% CC BY QUALITY.

Plugged through: CSG

District: 01

Signed

Jerry W Stapleton
(TECHNICIAN)
PART II

RECEIVED

MAY 24 2010

KCC DODGE CITY

Form CP-103