

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22235-00-00 \$ 152.75
Spot: SENWNWSE Sec/Twnshp/Rge: 19-18S-28W
2124 feet from S Section Line, 2221 feet from E Section Line
Lease Name: EITEL Well #: 1-19
County: LANE Total Vertical Depth: 4700 feet

Operator License No.: 31783
Op Name: MID-CONTINENT ENERGY OPERATING
Address: 100 W 5TH ST STE 450
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	300		WITH 200 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/23/2010 10:00 PM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: LARRY HINDERLITER Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: 1ST PLUG AT 2190' WITH 50 SX CMT. 2ND PLUG AT 1350' WITH 80 SX CMT. 3RD PLUG AT 660' WITH 50 SX CMT. 4TH PLUG AT 330' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: NONE
Date/Time Plugging Completed: 05/24/2010 12:00 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

1ST PLUG AT 2190' WITH 50 SX CMT. 2ND PLUG AT 1350' WITH 80 SX CMT. 3RD PLUG AT 660' WITH 50 SX CMT. 4TH PLUG AT 330' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

6/02/10
2010061186

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 28 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED
MAY 24 2010

Signed Jerry W Stapleton
(TECHNICIAN)
PIRATI

KCC DODGE CITY