

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-00263-00-00
Spot: S2SENE Sec/Twnshp/Rge: 28-8S-16W \$ 117.96
2970 feet from S Section Line, 660 feet from E Section Line
Lease Name: NORTH LATON UNIT Well #: 5-1
County: ROOKS Total Vertical Depth: 3445 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	280	0	130 SX
PROD	5.5	3225	0	75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/17/2010 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 1/4# flocele - 600# hulls - 11 sxs gel spacer. Perfs 1260' - 730' - 330'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/17/2010 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3026' - pumped 11 sxs gel spacer - followed with 75 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1275' - pumped 75 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 650' - pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface.
Pulled all tubing. Hooked onto 5 1/2" casing - pumped 45 sxs 60/40 pozmix - 4% gel.
Hooked to 10 3/4" x 5 1/2" annulus - pumped 20 sxs 60/40 pozmix - 4% gel.
S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3162	3166		
3159	3170		
3094	3105		

6/02/10
2010061189
RECEIVED
MAY 25 2010
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS HARRISON #1. ALLIED CEMENTING COMPANY-TICKET #41593.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

MAY 19 2010

DERBY OIL CO

#1 HARRISON

28-8-16W

S2 SE NE

Contr.

ROOKS County

E 1939

Comm 5-31-45

Comp 6-17-45

IP

60 BOPD

Tops	Depth	Datum
ANH	1200	
TOP	2803	
HEEB	3017	
KC	3058	
ARB	3428	
TD	3445	

Casing
 10" 280
 5" 3225

SSO 2903-09: Perf 12/3159-70
 12/3162-66: 400' WIH/14 hrs:
 36/3094-3105: A/500: 125' OIH/
 12 hrs: A/1500

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS