

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-00617-00-01  
Spot: NWSWNW Sec/Twnshp/Rge: 29-10S-20W  
3576 feet from S Section Line, 4726 feet from E Section Line  
Lease Name: WHISMAN Well #: 3  
County: ROOKS Total Vertical Depth: 3710 feet

# 120.58

Operator License No.: 33922  
Op Name: MUSTANG ENERGY CORPORATION  
Address: 2521 E 20TH ST  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	229	0	w/unknown sxs cmt
T1	2.375	3673		
L1	4.5	3684	0	w/75 sx cmt
PROD	5.5	3679	0	w/150 sxs cmt

Well Type: SWD UIC Docket No: D28546.0 Date/Time to Plug: 05/18/2010 10:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: RODNEY BRIN Company: MUSTANG ENERGY CORPORATIO Phone: (785) 628-3660

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/18/2010 10:50 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 4 1/2" casing - pumped 130 sxs 60/40 pozmix - 4% gel with 250# hulls.  
Max. P.S.I. 1000#.  
Cement to approximately 2,000'.  
Visually checked annulus - cement to surface.

Perfs:

6/02/10  
2010061190

RECEIVED  
MAY 24 2010  
WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS THOMAS #1. ALLIED CEMENTING COMPANY-TICKET #41692.

Plugged through: CSG

District: 04


Signed

Pat Bedore

(TECHNICIAN)

CM

BLACK DIAMOND OIL INC. 29-10-20W  
 1105 E. 30TH. #A #3 WHISMAN 'OWWO' NW SW NW  
 HAYS, KS. 67601  
 CONTR O.W.S. INC. CTY ROOKS  
 GEOL \_\_\_\_\_ FIELD TRICO  
 ELV 2114 KB SPD 11/27/86 <sup>CARD ISSUED</sup> 3/12/87 IP OIL WELL  
 00 617-00-01 ARB OH 3680-3687  
 API 15-163-01, 020



SMP	Top	Depth/Datum
HEEB	.....	3364-1250
TOR	.....	3384-1270
LANS	.....	3405-1291
BKC	.....	3626-1512
ARB	.....	3679-1565
ORTD	.....	3687-1573

OLD INFO: OPERATOR WAS VIRGINIA DRILLING, #1 THOMAS, SPD 10/10/52, SET 8 5/8 " 225, 5 1/2 " 3680, COMP AS P 25 BOPD, ARB OH 3680-3687 (CARD ISSUED 3/13/53), CONTR: UNKNOWN  
 NO CORES  
 DST (1) 3478-3489 (LANS) / OP 30", REC 40' GSY OCM, 50' OCM & WTR, 420' WTR, SIP 1220#, FP NA  
 DST (2) 3572-3616 (LKC) / OP 60", REC 123' HOCM, SIP 1170#, FP NA  
 MICT - CO, (ARB OH), AC 500 GAL, GSO, POP, P 25 BOPD  
 NEW INFO: FR 11/18/86, RE-ENTERED 11/27/86, WSH DWN TO ORTD, PROD CSG ALREADY IN HOLE, MICT - CO, TSTD 3680-3687 (ARB OH), SO, POP, OIL WELL (POTENTIAL NOT RPTD)

COPYRIGHT 1987  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS