

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-093-20474-00-00 \$ 91.98  
Spot: NWNWSENV Sec/Twnshp/Rge: 33-24S-36W  
1400 feet from N Section Line, 1502 feet from W Section Line  
Lease Name: HEDGE A Well #: 2  
County: KEARNY Total Vertical Depth: 2830 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	618		WITH 400 SX CMT
PROD	4.5	2828	827	WITH 225 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/07/2010 1:00 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed  
Plugging  
Method:

PLUG AT 1970'. TAG TOC. PLUG AT 660' WITH 80 SX CMT. PLUG AT 40' TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/11/2010 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

\*\*CASING LEAKS FROM 617-2828\*\* 5/7/10: PUMP 25 SX CMT & 200# HULLS THROUGH TBG AT 1978'. LET SET 3 DAYS. 5/10/10: TAG TOC IN 4 1/2" CASING WITH TBG AT 1601'. CIRCULATE HOLE FULL OF MUD. TOOH WITH TBG. PUMP 80 SX CMT AT 700'. PUMP 20 SX CMT AT 60'.

Perfs:

Top	Bot	Thru	Comments
2744	2750		COUNCIL GROVE
2718	2726		COUNCIL GROVE
2708	2713		COUNCIL GROVE
2679	2692		COUNCIL GROVE
2671	2676		COUNCIL GROVE
2655	2661		COUNCIL GROVE

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 28 2010

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

District: 01

Signed

*Ken Jehlik*  
(TECHNICIAN)

RECEIVED

MAY 17 2010

KCC DODGE CITY

Form CP223