

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21356-00-00
Spot: NENW Sec/Twnshp/Rge: 27-25S-9W
4673 feet from S Section Line, 3247 feet from E Section Line
Lease Name: GLOVER Well #: 1-27
County: RENO Total Vertical Depth: 3950 feet

\$ 128,38

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	216		195 SX
PROD	5.5	3942	2190	150 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: ROBIN AUSTIN Company: RAMA OPERATING Phone: (620) 234-5191

Proposed Plugging Method: PER KCC RULES

Plugging Proposal Received By: SHANE JONES Witness Type: NONE
Date/Time Plugging Completed: 02/24/2010 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3700' AND CAPPED WITH 5 SXS OF CEMENT. CUT CASING AT 2190' PULLED TO 1300' SPOTTED 35 SXS OF CEMENT; PULLED CASING TO 800' SPOTTED 35 SXS OF CEMENT; PULLED CASING TO 270' CIRCULATED TO SURFACE WITH 155 SXS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3810	3830	CSG	

6/02/10
2010061197

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 26 2010

CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND CEMENT OUT OF GREAT BEND KS -- TICKET #35845 POS-MIX 60/40 & 4% GEL

Plugged through: CSG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

✓