

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21257-00-00
Spot: NWSENW Sec/Twnshp/Rge: 22-25S-9W
1687 feet from N Section Line, 1900 feet from W Section Line
Lease Name: SHAFFER Well #: 1-22
County: RENO Total Vertical Depth: 3900 feet

\$ 126.75

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	182		185 SXS
PROD	5.5	3898		175 SXS

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: SHANE JONES Witness Type: PARTIAL
Date/Time Plugging Completed: 02/22/2010 1:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

2/19/2010 ~~SAVED~~ BACK TO 3800' CAPPED WITH 5 SXS OF CEMENT, CUT CASING PIPE OFF AT 2500'. 2/22/2010 PULLED CASING TO 1300' SPOTTED 35 SXS OF CEMENT, PULLED CASING TO 800' SPOTTED 35 SXS OF CEMENT, PULLED CASING TO 250' CIRCULATED 140 SXS OF CEMENT TO SURFACE. 2/24/2010 CHECKED TOP PLUG, FELL BACK 80'--TOPPED WITH 20 SXS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3844	3860	CSG	

6/02/10
2010061197

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 26 2010


CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, TICKET #35849 60/40 W/4% GEL POS MIX

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)