

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20857-00-00 # 194.19
Spot: SESENW Sec/Twnshp/Rge: 3-34S-29W
2310 feet from N Section Line, 2310 feet from W Section Line
Lease Name: DEEDS Well #: 1-3
County: MEADE Total Vertical Depth: 5975 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1465		WITH 635 SX CMT
PROD	4.5	5973	2703	WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/06/2010 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: TRACY BLACK Company: _____ Phone: (316) 215-1873

Proposed Plugging Method: PUT 100' SAND & 5 SX CMT ON TOP OF SAND BRIDGE. PLUG AT 1490' WITH 20 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/06/2010 11:00 AM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

WELL SQUEEZED FROM 3726-3900 PUMP 100' SAND & 4 SX CMT. 1ST PLUG AT 1490' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5747	5786		
3726	3900		

6/02/10
2010061212

RECEIVED

MAY 26 2010

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed Jack MacLaskey
(TECHNICIAN)

RECEIVED

MAY 11 2010

KCC DODGE CITY

Form CP-27