

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19239-00-03
Spot: NWENWSE Sec/Twnshp/Rge: 19-32S-3E
2576 feet from S Section Line, 1777 feet from E Section Line
Lease Name: CARTER WAITE Well #: 6
County: COWLEY Total Vertical Depth: 3675 feet

\$119.44

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1518		565 SX
COND	20	39		65 SX
L1	4.5	3460		280 SX
PROD	7	3124		750 SX

Well Type: EOR UIC Docket No: E23297.1 Date/Time to Plug: 04/21/2010 8:00 AM
Plug Co. License No.: 33608 Plug Co. Name: W.D. SHORT OIL CO., LLC
Proposal Rcvd. from: MIKE ANSTINE Company: W D SHORT OIL CO Phone: (620) 218-1822

Proposed Plugging Method: AS PER KCC RUELS & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 04/21/2010 10:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 3410', DUMP BAILED 5 SXS CEMENT ON TOP. RIH W/TBG @ 350', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 30 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 10:00 AM. 4-21-2010. CONSOLIDATED CEMENT TICKET #24370.

Perfs:

Top	Bot	Thru	Comments
3460	3675	OH	ARBUCKLE

6/02/10
2010061213

Remarks:

Plugged through: TBG

District: 02

RECEIVED

Signed

Duane Krueger

(TECHNICIAN)

JUN 02 2010

KCC WICHITA