

4-071127

API number: 15-109-20,573-00-00

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

W2 NW NE /4 SEC. 15, 12 S, 33 W  
660 feet from S section line  
2310 feet from E section line

Operator license# 5135

Lease Moore well # 1

Operator: John O. Farmer, Inc.

County Logan

Address: P.O. Box 352  
Russell, Kansas 67665  
John O. Farmer

Well total depth 4740 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 255 feet

154.05

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: Abercrombie Drilling - Allied Cement License# -

Address: Wichita, Kansas 67202 - Oakley, Kansas

Company to plug at: Hour: A.M. Day: 28 Month: October Year: 94

Plugging proposal received from: Tony Martin

Company: Abercrombie Drilling Phone: 913-483-3144

Were: 8 5/8" - 255' S.P. cwc. w/200 sxs. 60/40 pozmix - 2% gel - 3% c.c. By Allied Cement. Elv. 3124' - Anhy. 2617' - No circulation problems - Mud condition 48 vis. - 9.0 wt. - 8.8 W.L. - 2500 ppm cl at 4033'. Proposal - circulate hole - mud 42 to 45 vis. Order 190 sxs. 60/40 pozmix - 6% gel and 1/4# flocele per sack. Spot and displace all cement through drill pipe. No ar buckle - Miss well. 1st. plug 25 sxs. @ 2630' - 2nd. plug 100 sxs. @ 1570' - 3rd. plug 40 sxs @ 300' - 4th. plug 10 sxs. @ 40'. 15 sxs. in rathole circulate. Plugging Proposal Received by: Marion J. Schmidt Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour: 3:00A.M., Day: 28, Month: October, Year: 94

Actual plugging report: Abercrombie Drilling ordered 190 sxs. 60/40 pozmix - 6% gel - 1/4# flocele per sack - circulated hole - mud 48 vis spotted and displaced all cement through drill pipe with heavy mud between all plugs. 1st. plug @ 2630' w/25 sxs. cement. 2nd. plug @ 1570' w/100 sxs. cement. 3rd. plug @ 300' w/40 sxs. cement. 4th. plug @ 40' w/10 sxs. cement. 15 sxs. in rathole (circulated)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 03 1994  
11-03-1994

Remarks: Cemented by Allied Cement.  
Condition of casing(in hole): GOOD X BAD      Anhy. plug: YES X NO       
Bottom plug(in place): YES     , CALC     , NO      Dakota plug: YES X, NO       
Plugged through TUBING     , CASING X. Elevation:      GL     

I did X did not      observe the plugging.

Marion J. Schmidt  
(agent)

NOV 9 1994  
41584