

6-100476

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-109-20,550-00-00

C SW NW/4 SEC. 15-12-33W
3300 feet from S section line
4620 feet from E section line

Operator license# 05393

Lease: MICHAELIS # 2

Operator: A.L. Abercrombie Inc.

County: LOGAN

Address: 150 North Main
Suite 801
Wichita, KS

Well total depth: 4700 feet 152.75
Conductor pipe: inch @ feet
Surface pipe: 8 5/8 inch @ 326 feet

67202-1383

Well type: D&A

Plugging contractor: ABERCROMBIE RTD, INC.

License: 30684

Address: WICHITA, KANSAS

Company to plug at: Hour: ?? Day: Month: Year:

Plugging proposal received from: TONY MARTIN

Company: ABERCROMBIE RTD, INC. Phone:

Were: Spot all plugs through drill with heavy mud between all plugs.

1st plug @ 2610 feet with 25 sacks

Rat hole: 15 sacks

2nd plug @ 1560 feet with 100 sacks

Mouse hole: 0 sacks

3rd plug @ 375 feet with 40 sacks

Wiper plug @ 40 feet

4th plug @ 40 feet with 10 sacks

5th plug @ 0 feet with 0 sacks

Plugging proposal received by: DAVID WANN

Plugging operations attended by agent? [NONE]

Completed: hour: 3:30 PM 1 June 1993

Actual plugging report: Hole reported plugged as above

Order 190 sx 60/40 posmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 3109 G Anhydrite depth: 2609 feet, Anhy. plug: T

Dakota plugged: T Bottom hole plug in place (A/E/N): N

Plugged through drill pipe: T

Arbuckle: Cemented by: ALLIED CMT.

I did[] / did not[X] observe the plugging.

DAVID WANN

D# (agent)

form CP-2/3

6-18-93

37953

6-1

RECEIVED

06-15-1993
JUN 15 1993