

3-23  
4-050281

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-109-20,644-0000

SE NW NE /4 SEC. 18, 12 S, 33 W  
4291 feet from S section line  
1635 feet from E section line

Operator license# 5003

Lease: Bouziden "A" Well # 1-18

Operator: McCoy Petroleum Corporation

County: Logan 156.00

Address: 3017 N. Cypress Street  
Wichita, Kansas 67226-4003  
316-636-2737

Well total depth 4800 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 219 feet

Aband. oil well\_\_\_, Gas well\_\_\_, Input well\_\_\_, SWD\_\_\_, D & A X

Plugging contractor: Allied Cementing Inc. License# -

Address: \_\_\_\_\_

Company to plug at: Hour: P.M. Day: 23 Month: March Year: 1997

Plugging proposal received from: Brad

Company: Sweetman Drilling Phone: \_\_\_\_\_

Were: Order 200 sxs 60/40 pozmix - 6% gel with 1/4 lb. flo-seal pr. sack.

RECEIVED  
MAR 27 11:42  
03-27-1997

Plugging Proposal Received by: Marvin Miller

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour 12:30 P.M. Day: 23, Month: March, Year: 1997

Actual plugging report: \_\_\_\_\_

1st. Plug at 2645' w/25 sxs.

2nd. Plug at 1595' w/100 sxs.

3rd. Plug at 270' w/40 sxs.

4th. Plug at 40' w/10 sxs. and wiper plug.

Rathole 15 sxs.

Mousehole 10 sxs.

Remarks: \_\_\_\_\_

Condition of casing(in hole): GOOD \_\_\_\_\_ BAD \_\_\_\_\_ Anhy. plug: YES X NO \_\_\_\_\_

Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_

Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_ Elevation: 3145 GL

I did[ ] / did not[ X ] observe the plugging.

Marvin Miller  
(agent)

47836