

3-30

4-070091

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-109-20,666-00-00

E2 E2 SW /4 SEC. 18, 12 S, 33 W  
1320 feet from S section line  
2970 feet from E section line

Operator license# 4629

Lease: Irwin Well # 1-18

Operator: Brito Oil Company, Inc.

County: Logan 154.86

Address: 120 S. Market - Suite #400  
Wichita, Kansas 67202

Well total depth 4765 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 221 feet  
W/150 sxs.

ABAND. oil well, Gas well, Input well, SWD, D&A X

Plugging contractor: White & Ellis Drilling, Inc. License# 5420

Address: P.O. Box 48848 - Wichita, Kansas 67201

Company to plug at: Hour: P.M. Day: 30 Month: March Year: 1998

Plugging proposal received from: Judy

Company: White & Ellis Drilling, Inc. Phone: 316-263-1102

Were: Ordered 190 sxs 60/40 pozmix - 6% gel - 1/4# floseal per sack - one 8 5/8 W.P.  
Spot plug through drill pipe with heavy drilling mud between all plugs.  
RTD 4765'.

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 1:30 P.M., Day: 30, Month: March, Year: 1998

Actual plugging report: No ar buckle cut.

1st. Plug at 2635' w/25 sxs. - Anhydrite 2623' - 2646'.

2nd. Plug at 1592' w/100 sxs. - Dakota Base 1292'.

3rd. Plug at 271' w/40 sxs. - Surface pipe at 221' + 50'.

4th. Plug at 40' w/10 sxs with 8 5/8" wiper plug.

15 sxs in rathole.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING Elevation: 3142 GL

I did [ ] / did not [ X ] observe the plugging.

*Richard Williams*

(agent)

Form CP-2/3

INVOICED

DATE 4-8-98

INV. NO. 50335

04-02-1998