

4-090505

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-109-20,554-00-00

SE /4 SEC. 19, 12 S, 33 W
330 feet from S section line
2340 feet from E section line

Operator license# 5285 Lease Beckman well # 1

Operator: Dane G. Hansen Trust County Logan

Address: P.O. Box 187 Well total depth 4850 feet ^{157.62}
Logan, Kansas 67646 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 248 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Chief Drilling, Inc. License# 5886

Address: Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 25 Month: May Year: 93

Plugging proposal received from: Harold Dinkel

Company: Chief Drilling, Inc. Phone:

Were: Order 200 sks. 60/40 pozmix - 6% gel. and 2 sks. celloflake.
Spot all plugs through drill pipe with heavy mud between all
plugs.

Plugging Proposal Received by: Ed Schumacher

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 1:30A.M., Day: 26, Month: May, Year: 93

Actual plugging report:

- 1st. plug @ 2645' w/ 25 sks.
- 2nd. plug @ 1615' w/100 sks.
- 3rd. plug @ 300' w/ 40 sks.
- 4th. plug @ 40' w/ 10 sks.
- 15 sks. in rathole.
- 10 sks. in mousehole.

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1993
06-21-1993
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Allied Cementing. (No ar buckle)

Condition of casing(in hole): GOOD BAD Anyh. plug: YES X NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING . Elevation: 3163 GL

I did[] / did not[X] observe the plugging. Ed Schumacher

ES
(agent)

6-29-93
38021