

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20272-00-00
Spot: CNENEŠW Sec/Twnshp/Rge: 22-12S-33W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: GILKERSON Well Number: 1
County: LOGAN Total Vertical Depth: 4810 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

Conductor Pipe: Size feet: 3156.33
Surface Casing: Size 8.625 feet: 305 215 SX CMT
Production: Size 5.5 feet: 4809 250 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/04/2002 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: Ordered out 160 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 03/04/2002 4:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Set cast iron bridge plug at 4040' and topped with 5 sxs cement using a dump bailer.
Shot casing at 1650' - would not free - pulled up to 1430' - shot free.
Spotted 80 sxs cement with 500# hulls.
Pulled up to 500' and spotted 30 sxs cement.
Pulled up to 200' and circulated cement with 40 sxs.
POOH. Topped off with 10 sxs cement.

RECEIVED
MAR 08 2002
KCC WICHITA
03-08-2002

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

INVOICE

Form CP-2/3

DATE Mar 8-02

INV. NO. 2002061503

MAR 06 2002

REPLACEMENT CARD

BEREXCO-BEREN CORPORATION
970 FOURTH FINANCIAL CENTER
WICHITA, KS 67202

#1 GILKERSON


22-12-33W
NE NE SW

CONTR KANDRILCO, INC.

CTY LOGAN

GEOL STEVE KREIDLER

FIELD WC(OWEN EAST DISC)



ELV 3098 KB SPD 3/14/83

CARD ISSUED 6/16/83

IP P 110 BOPD

3090 GL

LKC 4264-4292-0A

API 15-109-20,272

LOG	Tops	Depth/Datum
ANH		2576 + 522
B/ ANH		2600 + 498
TARK		3650 - 552
TOP		3778 - 680
HEEB		4005 - 907
TOR		4028 - 930
LANS		4048 - 950
MUNCIE CRK		4197 - 1099
STARK		4278 - 1180
BKC		4347 - 1249
MARM		4384 - 1286
PAW		4475 - 1377
FT SC		4532 - 1434
CHER		4560 - 1462
JH ZN		4604 - 1506
BASAL PENN SD		4671 - 1573
MISS		4690 - 1592

8 5/8 " 305 / 215 SX; 5 1/2 " 4809 / 250 SX
 DST (1) 4016-4040 (TOR) / 45-45-60-45, REC 290' MW, SIP 1009-943#, FP 33-98 / 31-153#
 DST (2) 4255-4286 (LKC) / 60-60-60-60, REC 1070' OIL, 180' GSY OCM, SIP 1238-1216#, FP 87-273 / 306-393#
 DST (3) 4280-4300 (LKC 'K') / 60-60-60-60, 900' GIP, REC 804' OIL, 66' WTR, SIP 1216-1183#, FP 87-175 / 229-317#
 DST (4) 4510-4548 (PAW, FT SC) / 60-60-60-60, 120' GIP, REC 300' OIL, 60' HOCM (45% OIL), 10' OCM (15% OIL), SIP 1107-1085#, FP 55-120 / 131-164#
 SPERG DOL 4775-1677
 LTD 4808-1710
 RTD 4810-1712

INFO RELEASED: 8/25/83 - ADDED LOG TOPS & DST INFO
 NOTE: 5/5/83 - ORIGINALLY FIRST REPORTED AS BEREN CORPORATION AS OPERATOR

(over)