

4- 031773

10-9

228

R

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-109-20,511-00-00  
SE NE NW /4 SEC. 29, 12 S, 33 W  
4290 feet from S section line  
2970 feet from E section line

Operator license# 3581 Lease Smith well # 1-29

Operator: Red Oak Energy, Inc. County Logan

Address: 200 W. Douglas Well total depth 4760 feet 154.70  
Wichita, Kansas 67202 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 269 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Services License# -

Address: Oakley, Kansas

Company to plug at: Hour: P.M. Day: 9 Month: October Year: 92

Plugging proposal received from: Kevin Davis

Company: Red Oak Energy, Inc. Phone: \_\_\_\_\_

Were: Order 200 sx. 60/40 pozmix - 10% gel. - 500# hulls.  
Hole open to perf.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 2:30P.M., Day: 9, Month: October, Year: 92

Actual plugging report: 8 5/8" set @ 269' w/170 sx. 4 1/2" set @ 4759'  
w/250 sx. F.O. Tool @ 2625' w/415 sx. Perf. 4120' - 4288'.  
P.B.T.D. 4120'. Squeezed 4 1/2" w/200 sx. cement blend with 350# hulls  
mixed in to Max. P.S.I. 1000#. Close in P.S.I. 600#. Plug complete.  
Couldn't pump into 8 5/8".

Remarks: \_\_\_\_\_

Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO   
Bottom plug(in place): YES  CALC  NO  Dakota plug: YES  NO   
Plugged through TUBING , CASING . Elevation: \_\_\_\_\_ GL \_\_\_\_\_

I did[  ] / did not[  ] observe the plugging. Carl Goodrow

(agent)

10-30-1992  
OCT 26 1992

11-17-92  
36793