

6 020167

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 109-20,350-00-00
SW NE NW SEC. 28, T 12 S, R 33 W/E
SE
4290 feet from N/S section line
SE
3630 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5285

Lease Name Hueftle Well # 3

Operator: The Dane G. Hansen Trust

County Logan

Name & Address Box 187

Well Total Depth 4740 154.05 feet

Logan, Ks. 67646

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 363

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Galloway Drilling License Number 5783

Address Wichita

Company to plug at: Hour: PM Day: 26 Month: September Year: 1984

Plugging proposal received from Carl Mcauire

(company name) Galloway Drilling (phone) (316) 263-1793

were: Order 185 sks 50/50 pozmix 6% gel 3% cal. cl., 2 sks cello-flake and 8 5/8" plug.

Spot drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

_____ Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XX

Operations Completed: Hour: 7:45 P.M Day: 26 Month: September Year: 1984

ACTUAL PLUGGING REPORT

- 1st plug @ 2640 w/25 sks
- 2nd plug @ 1580 w/100 sks and 2 sks cello-flake
- 3rd plug @ 380 w/40 sks
- 4th plug @ 40 w/10 sks
- 10 sks in Rat Hole

10-01-1984
OCT 01 1984

Remarks: Cemented by Allied
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 10-5-84
INV. NO. 4054
9-26

Signed Gerald Balthazar
(TECHNICIAN) 9-28-84 16