

8-14

4-041912

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-109-20,653 ~~00-00~~

SE NW NW /4 SEC. 28, 12 S, 33 W
4290 feet from S section line
4290 feet from E section line

Operator license# 5285

Lease: Hueftle Well # 5

Operator: Dane G. Hansen Trust

County: Logan 152.10

Address: P.O. Box 187
Logan, Kansas 67646

Well total depth 4680 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 330 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Discovery Drilling License# 31548

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 14 Month: August Year 1997

Plugging proposal received from: Tom Alm

Company: Discovery Drilling Phone:

Were: Order 200 sxs 60/40 pozmix with 6% gel - 1/4# floseal per sack.
Spot plug through drill pipe with heavy mud between all plugs.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 2:15 A.M., Day: 14, Month: August, Year: 1997

Actual plugging report:

- 1st. plug at 2640' w/25 sxs.
- 2nd. plug at 1580' w/100 sxs.
- 3rd. plug at 380' w/40 sxs.
- 4th. plug at 40' w/10 sxs.
- 15 sxs in rathole.
- 10 sxs in mousehole.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING Elevation: 3137 GL

I did[] / did not[X] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED

8-27-97

48863

08-26-1997