

6030434

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-109-20,278-00-00  
CNWSW SEC. 27, T. 12 S, R. 33 W

1980 feet from (S) section line  
4620 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Smith "A0" Well # 1

Operator: Donald C Slawson  
Name &  
Address 200 Douglas Bldg.  
Wichita, Kansas  
67202

County Logan  
Well Total Depth 4830 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 327'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address Chase Kansas 67524

Company to plug at: Hour: PM Day: 6 Month: 5 Year: 19 85

Plugging proposal received from Ronnie  
(company name) Kelso Casing (phone) \_\_\_\_\_

were: 8 5/8" at 327' w/ 225' of 4 1/2" at 4829' w/ 275' of Perf. 4304-09, 4063-66  
Order Com. Cem. & sand Plug off bottom shoot pipe and Recover.  
Order 180' of 50/50 polyblend 3% cc, 40' of gel, 4' of Hulls, 8 5/8" W.P.  
Sun Cement Co. Wellrock water trucks

Plugging Proposal Received by Carl Goodnow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:40 PM Day: 6 Month: 5 Year: 19 85

ACTUAL PLUGGING REPORT Pumped 50' of Cement with W.P. spotted @ 4000'  
Behote from 3000' to 1420' Recovered pipe. Top plug, Pumped down 8 5/8"  
w/ 4' of hulls + 18' of gel, 100' of Cem. mix. 22' of gel. 8 5/8" W.P. 80' of Cem. mix.  
Max. Press. 500# Shut in 300# Plug Complete.

MAY 28 1985  
CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 6-6-85  
8395

Signed Carl Goodnow  
(TECHNICIAN)

4  
5-28-85  
MOR