

15-051-03423-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ellis County, Sec. 24 Twp. 11S Rge. (E) 17 (W)

Location as "NE/CNW&SW&W" or footage from lines 330'S & f N/4 Corner

Lease Owner Cities Service Oil Company

Lease Name Colahan "A" Well No. 12

Office Address Box 553 Russell, Kansas 67665

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 4-29 1940

Application for plugging filed 11-12 1971

Application for plugging approved 11-15 1971

Plugging commenced 12-30 1971

Plugging completed 1-26 1972

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production February 19 66

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Leo Massey

Producing formation Arbuckle Depth to top 3396' Bottom 7' Pen. Total Depth of Well 3403 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1042'	None
				5 1/2"	3397'	2078'
RECEIVED STATE CORPORATION COMMISSION APR 6 - 1972 CONSERVATION DIVISION Wichita, Kansas						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand to 3385' and 5 sx. cement 3385' to 3350'. Shot off 5 1/2" casing at 2300' and pulled 71 joints. Halliburton pumped 20 sx. gel, 3 sx. hulls 1225' to 425', 8 5/8" plug, 85 sx. cement 425' to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co., Inc.

Address Chase, Kansas


STATE OF Kansas, COUNTY OF Russell, ss.

E. W. Peterman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *E. W. Peterman*

Box 553 Russell, Kansas 67665 (Address)

Subscribed and sworn to before me this 4th day of April, 19 72



10-5-72

James F. Kuyper
Notary Public.

WELL RECORD

Company Cities Service Oil Co. Well No. 12 Farm Colahan "A"
 Location 330' South of N/4 Corner Sec. 24 T. 11 R. 17-W
 Elevation 1906 County Ellis State Kansas
 Drig. Comm. April 7, 1940 Contractor Mabee Oil & Gas Company
 Drig. Comp. April 29, 1940 Acid 500 gallons acid April 30, 1940
 T. D. 3403' Initial Prod. Echo-Meter: 3700 oil, no water, 24 hours.

CASING RECORD:

8-5/8" 1042' cem. 225 sx Monarch,
 25 sx High Early & 10
 sx Aquadrel.
 8-1/2" 3397' cem. 100 sx. Ideal cem.

Corr. Top Arbuckle 3396' (-1490)
 Penetration 7'
 Total Depth 3403' (-1497)

FORMATION RECORD:

red bed & shells	0-35
shale & shells	605
sand	690
shale & shells	1042
red bed & shells	1070
lime	1110
shale & shells	1455
shale & shells & salt	1539
shale & salt	1650
shale & shells	1800
lime	1900
lime & shale	2874
lime	3265
lime broken	3338
shale	3400
sand	3402
lime (top Arbuckle 3402)	3403
Rotary T.D. 3403-3397 S.L.M.	
dolomite	3397-3403 T.D.

FILLUP: 200' in 13 mins.
 2000' in 1 hr. 50 mins.
 2525' in 2 hrs. 5 mins.
 2800' in 3 1/2 hours

GYFO: 500' 00
 1000' 00
 1500' 00
 2000' 00
 2500' 00
 3000' 00

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 15 1971
 CONSERVATION DIVISION
 Wichita, Kansas