

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-109-20,081-00-00

LEASE NAME Johnston #1

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER SW SE

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 6 TWP. 12s RGE. 33w (E) or (W)

COUNTY Logan

Date Well Completed 8/8/77

Plugging Commenced 6/3/85

Plugging Completed 6/5/85

LEASE OPERATOR Chief Drilling Co., Inc.

ADDRESS 905 Century Plaza, Wichita, Ks. 67202

PHONE# (316) 262-3791 OPERATORS LICENSE NO. 5886

Character of Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	286'	none
				4 1/2"	4798'	2141'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged bottom with 4 sacks cement, sand to 4280' & 4 sacks cement. Shot pipe at 3012', 2500', & 2141'. Pulled 66 joints of pipe. Plugged well with 4 hulls;

40 gel, & 140 sacks 50/50 poz 6% gel 3% c.c.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice

R. Darrell Kelso

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 10th day of June, 19 85

Irene Hoover
Notary Public

My Commission Expires:



WELL LOG.

15-109-20081-00-00

CHIEF DRILLING CO., INC.
905 Century Plaza
Wichita, Kansas 67202

#1 JOHNSTON
SW SE Sec. 6-12S-33W
Logan County, Kansas

CONTRACTOR: Company Tools
CASING RECORD: 8 5/8" set @ 286' w/180 sx.

COMMENCED: July 26, 1977
COMPLETED: August 8, 1977

FORMATION	FROM	TO	ELEVATIONS
Surface Mud	0	292	3176 Gr.
Sand & Shale	292	2584	3178 D.F.
Shale	2584	2662	3181 K.B.
Anhydrite	2662	2686	
Shale	2687	4175	
Shale & Lime	4175	4185	
Lime	4185	4230	
Lime & Shale	4230	4280	
Lime	4280	4800	
RTD	4800		

~~FORMATION LOG~~

ELECTRIC LOG TOPS:

Anhydrite	2664 +	517
Base Anhydrite	2686 +	495
Heebner	4068 -	887
Toronto	4094 -	913
Lansing	4110 -	929
BKC	4407 -	1226
Cher. Shale	4623 -	1442
Miss.	4744 -	1563
LTD	4800 -	1619


RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1985
05-24-1985
CONSERVATION DIVISION
Wichita Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SW SE of Section 6-12S-33W,
Logan County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.


Jim Robinson, Vice-President

Subscribed and sworn to before me this 11th day of August, 1977.

MARILYN SINARD
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. APR. 30, 1979


Marilyn Sinard Notary Public