

LEASE NAME Bertrand

WELL NUMBER 1

SPOT LOCATION NW NE

SEC. 7 TWP. 12 RGE. 33(E)

COUNTY Logan

Date Well Completed 9-20-77

Plugging Commenced 10-25-89

Plugging Completed 10-26-89

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Beren Corp.

ADDRESS Box 723 Hays, Kansas 67601

PHONE # 913 628 6101 OPERATORS LICENSE NO. 5364

Character of Well Oil
 (Oil, Gas, D&A, SMD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas 67601

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4764

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	332	8 5/8	--	--
	Casing	0	4764	4 1/2	--	--

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Perf. 2 holes 2679 base annulus and 2 holes 1800' base Dakota. Run tubing to 2600' and fill casing with cement to surface. Pull tubing. Hook up to casing and squeeze in cement to 200' SIP used 150 sacks total. Hook up to surface casing and pump in 100 sacks and Shut in at 250. Rig down and move.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Beren Corp. License No. 5364

Address Box 723 Hays, Kansas 67601
BJ Titan cementers

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Crawford
 (Address) Box 723 Hays, Ks 67601



RECEIVED
 STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 30 day of October, 1989

10-31-1989
 CONSUMER DIVISION
 Wichita, Kansas

Premay Smith
 Notary Public

My Commission expires: _____