

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-109-20099-00-00  
 API NUMBER 3-13-78

LEASE NAME Bertrand

WELL NUMBER 2

SPOT LOCATION NE NE

SEC. 7 TWP. 12 RGE. 33 (E) or (W)

COUNTY Logan

Date Well Completed 3-13-78

Plugging Commenced 10-27-89

Plugging Completed 10-28-89

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Beren Corp.

ADDRESS Box 723 Hays, Kansas 67601

PHONE # (913) 628 6101 OPERATORS LICENSE NO. 5364

Character of Well oil  
 (Oil, Gas, D&A, SMD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas 67601

Is ACO-1 filed?                      If not, is well log attached?                     

Producing formation                      Depth to top                      bottom                      T.D. 4750

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	296	8 5/8	--	--
	Casing	0	1740	4 1/2		1430'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Set CIBP at 4000'. Load hole with water. Perf. 2 holes 2670 and 2 holes 1800'. Shot off casing at 1410'. Casing free. Pulled 33 jts. Finish pulling casing and plug well with 225 sacks 65/35 posmix, 10% gel down 8 5/8 casing. Rig down and move off.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Beren Corp. License No. 5364  
 Address Box 723 Hays, Kansas 67601

BJ. Titan cementer

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED  
 STATE CORPORATION COMMISSION  
 10-31-1989  
 OCT 31 1989

(Signature) Ted Crawford  
 (Address) Box 723 Hays, Ks 67601

SUBSCRIBED AND SWORN TO before me this 30 day of October 1989

CONSERVATION DIVISION  
 Wichita, Kansas

Rosemary Smith  
 Notary Public

My Commission expires: 5-1-1991