

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-109-20,547-00-00

LEASE NAME Beagley

WELL NUMBER 1-22

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

660' Ft. from S Section Line

660' Ft. from E Section Line

SEC. 2 TWP. 12S RGE. 33 (E) or (W)

COUNTY Logan

LEASE OPERATOR Brito Oil Company, Inc.

ADDRESS 200 E. 1st, Suite 208, Wichita, KS 67202

PHONE# (316) 263-8787 OPERATORS LICENSE NO. 4629

Date Well Completed _____

Character of Well D&A

Plugging Commenced 1-4-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-4-93

The plugging proposal was approved on 1-4-93 (date)

by Dennis Hamel (KCC District Agent's Name).

is ACO-1 filed? No If not, is well log attached? _____

Producing Formation Lansing, Marm, Cherokee Depth to Top _____ Bottom _____ T.D. 4750

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	222'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
Fill w/heavy mud; set 1st plug @ 2600'-2500' w/25 sx; 2nd plug @ 1530'-1130' w/100 sx; 3rd plug @ 260'-100' w/40 sx; 4th plug @ 40'-surface w/10 sx; w/wiper plug; rathole 15 sx; Total 190 sx 60-40 posmix 6% gel 1/2# celoflake.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Suite 801, Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brito Oil Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) of Brito Oil Company, Inc. above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801, Wichita, KS 67202



SUBSCRIBED AND SWORN TO before me this 21st. day of January, 19 93

Angela Woodard
Notary Public

My Commission Expires: March 20, 1993

RECEIVED
STATE CORPORATION COMMISSION
01-22-1993
10:22 1993
CONS. DIVISION
WICHITA, KANSAS