

STATE OF KANSAS
STATE CORPORATION COMMISSION
11 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-109-20,272-00-00

LEASE NAME Gilkerson

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2310 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 22 TWP. 12S RGE. 33W (E) or (W)

COUNTY Logan

LEASE OPERATOR BEREXCO, INC.

ADDRESS P.O. Box 20380 Wichita, Kansas 67208

PHONE (316) 265-3311 OPERATORS LICENSE NO. 5363

Date Well Completed _____

Character of Well Oil

Plugging Commenced 2-28-02

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-4-02

The plugging proposal was approved on _____ (date)

Jay Pfiefer (KCC District Agent's Name).

ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 4810'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	313'	None
				5-1/2"	4809'	1430'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material was used, state the character of same and depth placed, from _____ feet to _____ feet each section.
Set cast iron bridge plug @4040' with 2 sacks cement on top. Shot pipe @2000', 1800', 1600' and 1430', pulled 1 joint, pumped 80 sacks cement, pulled up to 500', pumped 30 sacks cement, pulled up to 200', pumped 40 sacks cement and circulated to surface. Topped off with 10 sacks cement. 60/40 pos. 10% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 11th day of March 2002

[Signature]
Notary Public

My Commission Expires:



CR