

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev.03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-109-20,551-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Abercrombie Drilling, Inc. KCC LICENSE # 5422
(owner/company name) (operator's)
ADDRESS 150 N. Main, Suite 801 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 262-1841

LEASE Koch B WELL# #1 SEC. 9 T. 12S R. 33 (East/West)

SE - C - SE - SW SPOT LOCATION/QQQQ COUNTY Logan

554' FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

3194' FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 343.50' CEMENTED WITH 60-40 posmix-235 sx SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 3113'/3118' T.D. 4760' PBDT _____ ANHYDRITE DEPTH 2616' (+502')
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 2630' w/25 sx; 2nd plug @ 1560' w/100 sx; 3rd plug @ 400' w/80 sx; 4th plug @ 40' solid bridge w/rubber plug w/10 sx; rathole w/15 sx. Total 190 sx 60-40 posmix 6% gel 2 sx Floseal.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Tony Martin PHONE# (913) 743-5443

ADDRESS 533 N. Main, City/State Wakeeney, KS 67672

PLUGGING CONTRACTOR Abercrombie RTD, Inc. KCC LICENSE # 30684
(company name) (contractor's)

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Began @ 12:30 p.m. 6-12-93

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 7-27-93 AUTHORIZED OPERATOR/AGENT: Jack K. Wharton (signature)

RECEIVED
STATE CORPORATION COMMISSION
AUG - 4 1993
08-04-1993