

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev.03/92

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-109-20,511-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Red Oak Energy, Inc. KCC LICENSE # 3581 10-92

ADDRESS 200 W. Douglas, Suite 507 (owner/company name) CITY Wichita, (operator's)

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 265-9925

LEASE Smith WELL# 1-29 SEC. 29 T. 12 S. R. 33 (East/West)

SE - NE - NW - \_\_\_\_\_ SPOT LOCATION/QQQQ COUNTY Logan

4290 FEET (in exact footage) FROM (S) (circle one) LINE OF SECTION (NOT Lease Line)

2970 FEET (in exact footage) FROM (E) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL \_\_\_\_\_ D&A \_\_\_\_\_ SWD/ENHR WELL \_\_\_\_\_ DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 269' CEMENTED WITH 170 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 4759' CEMENTED WITH 250 (1) SACKS

(1) plus 415 sx through FO Tool @ 2625'. Top of cement @ 200' FS.  
LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: ~~pfs: 4286-88' BP @ 4120' pfs: 4086-91'~~

ELEVATION 3146 K.B. T.D. 4760' PBTD 4120' ANHYDRITE DEPTH 2555'  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING Put 50' cement plug from 4090' up to 4040'; mud to 50' FS; cement 50' to surface. Cut off casing below plow depth.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Kevis Davis PHONE# (316) 265-9925

ADDRESS as above City/State \_\_\_\_\_

PLUGGING CONTRACTOR none needed KCC LICENSE # \_\_\_\_\_ (contractor)

ADDRESS \_\_\_\_\_ PHONE # ( ) \_\_\_\_\_

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) NA

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-110) WILL BE GUARANTEED BY OPERATOR OF WELL

DATE: Sept. 14, '92 AUTHORIZED OPERATOR/AGENT: Kevin C. Davis

(signature)  
Kevin C. Davis, Pres./Geologist

RECEIVED  
STATE CORPORATION COMMISSION  
KCC LICENSE # \_\_\_\_\_  
SEP 16 1992  
09-16-1992  
CONSERVATION DIVISION  
WICHITA, KANSAS

4)

Joan Finney  
Governor

Jim Robinson  
Chairman

F. S. Jack Alexander  
Commissioner

Rachel C. Lipman  
Commissioner

Judith McConnell  
Executive Director

Brian Moline  
General Counsel



# Kansas Corporation Commission

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

September 30, 1992

Red Oak Energy Inc  
200 W Douglas 507  
Wichita KS 67202

Smith 1-29  
API 15-109-20,511-00-00  
4290'FSL 2970'FEL  
Sec. 29-12-33W  
Logan County

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000. If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams  
Production Supervisor

Conservation Division  
William R. Bryson  
Director  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, Kansas 67202-1286  
Telephone (316) 263-3238

District: #4 2301 E. 13th  
Hays, KS 67601  
(913) 628-1200