

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 109-20653 0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR THE DANE G. HANSEN TRUST KCC LICENSE # 5285
(owner/company name) (operator's)

ADDRESS P.O. Box 187 CITY Logan

STATE Kansas ZIP CODE 67646 CONTACT PHONE # (785) 689-4816

LEASE Hueftle WELL# 5 SEC. 28 T. 12s R. 33w ~~NE~~ (West)

- SE - NW - NW SPOT LOCATION/XXXX COUNTY Logan

4290 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

4290 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 330.18 CEMENTED WITH 200 SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 3137/3145 T.D. 4681 PSTD _____ ANHYDRITE DEPTH (2623/2645)
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING (1st Plug @ 2640'w/25sks)(2nd Plug @ 1580'w/100sks)(10sks In Mouse)
(3rd Plug @ 380'w/40sks)(4th Plug @ 40'w/10sks)(15sks In Rat Hole) By Allied Cementing

200sks 60/40Poz 6%Gel w/1/4#FS/sk Completed @ 2:15AM 8/14/97
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No Log IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Thomas H. Alm PHONE# (785) 625-5183

ADDRESS 1922 Whittier City/State Hays, Kansas 67601

PLUGGING CONTRACTOR DISCOVERY DRILLING, INC. KCC LICENSE # 31548
(company name) (contractor's)

ADDRESS P.O. Box 763 Hays, Kansas 67601 PHONE # (785) 623-2920

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 8/14/97 2:15AM

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 9/4/97 AUTHORIZED OPERATOR/AGENT: [Signature]
(signature)

09-05-1997