

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-24278-00-00
Spot: SENWSW Sec/Twnshp/Rge: 21-33S-3E
1630 feet from S Section Line, 4275 feet from E Section Line
Lease Name: JOHNSON Well #: 8-A
County: COWLEY Total Vertical Depth: 3390 feet

110.18

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	321		260 SX CMT.
PROD	5.5	3390	1189	200 SX CMT.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/08/2010 8:00 AM
Plug Co. License No.: 33608 Plug Co. Name: W.D. SHORT OIL CO., LLC
Proposal Rcvd. from: MIKE ANSTINE Company: W D SHORT OIL CO Phone: (620) 218-1822

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 04/09/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 3310', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 25 SXS 60/40 POZMIX 4% GEL, 2% CC AND DISPLACED IN CASING. TAGGED CEMENT @ 2930'. CUT CASING @ 1189', LAYED DOWN 56 JOINTS OF 5-1/2" CASING. RIH W/TBG @ 350', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 150 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 P.M. 4-9-2010. CONSOLIDATED CEMENT TICKET #24110.

Perfs:

Top	Bot	Thru	Comments
3246	3313	OH	


6/02/10
2010061213

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED
JUN 02 2010
KCC WICHITA

✓