

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-02830-00-00
Spot: NENWSW Sec/Twnshp/Rge: 35-24S-20E #35. -
2230 feet from S Section Line, 4520 feet from E Section Line
Lease Name: KRIEGER Well #: W 6
County: ALLEN Total Vertical Depth: 800 feet

Operator License No.: 8866

Op Name: MCFADDEN, JACK W. DBA MCFADDE

Address: PO BOX 394
IOLA, KS 66749

Well Type: EOR

UIC Docket No: E14856.30

Date/Time to Plug: 04/08/2010 10:00 AM

Plug Co. License No.: 5491

Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP

Proposal Rcvd. from: MIKE WIMSETT

Company: W & W PRODUCTION

Phone: (620) 431-5970

Proposed Plugging Method: Wash pipe down inside and outside of 2" casing, pull pipe out, perforate at 600', 300' & 150', ran 1" pipe inside casing to 800', outside to 150', circulate portland cement to surface, pull pipe out and top off well with portland cement.

Plugging Proposal Received By: JOHN ALMOND

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 04/08/2010 12:00 PM

KCC Agent: JOHN ALMOND

Actual Plugging Report:

Perfs:

Wimsett washed 1" pipe down inside 2" casing to 800', washed 1" pipe down the backside of 2" casing to 150', pulled 1" pipe out, perforated casing at 600', 300' & 150', ran 1" pipe back inside 2" casing to 800', and ran 1" pipe down backside of 2" casing to 150', circulated portland cement to surface, pulled 1" pipe out, topped of well with portland cement. Plugged well with 70 sacks of portland cement.

RECEIVED

JA

KCC Chanute Dist. #3

6/03/10
2010061184

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 28 2010

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed

John Almond
(TECHNICIAN)