

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23247-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 6-12S-15W *\$ 112.29*
2280 feet from S Section Line, 450 feet from W Section Line
Lease Name: SUSAN Well #: 6-1
County: RUSSELL Total Vertical Depth: 3455 feet

Operator License No.: 33335
Op Name: IA OPERATING, INC.
Address: 9915 W 21ST ST, STE B
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	929	0	w/450 sxs cmt
T1	2.375	3220		
PROD	5.5	3435	1270	w/200 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/24/2010 9:00 AM
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC
Proposal Rcvd. from: MIKE STANTON Company: IA OPERATING, INC. Phone: (316) 721-0036

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.
Shot 5 1/2" casing off at 1270'.
Sanded off from 3455' to 2530'.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/24/2010 2:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked onto 5 1/2" casing - pumped 150 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled 5 1/2" casing to 910' - pumped 100 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface.
Pulled 5 1/2" casing out of the hole.
Topped off 8 5/8" surface pipe w/30 sxs 60/40 pozmix - 4% gel.

Perfs:

Top	Bot	Thru	Comments
3198	3202		
3167	3174		
3147	3151		
3125	3128		
3074	3078		
2959	2962		
2722	2726		

6/01/10
2010061177

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3836.

Plugged through: CSG

District: 04

Signed Pat Bedore
(TECHNICIAN)

CM

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 27 2010

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

MAY 25 2010

Replacement Card

IA OPERATING
WICHITA KS 67212

6-12S-15W
2280'FSL & 450'FWL, SEC
KANSAS

#6-1 SUSAN

Cty: RUSSELL
Site: 5 S & 6 W OF PARADISE KS
Field: FAIRPORT EXT (1/2 W)

Spot: SW NW NW SW API 15-167-23247
Lat/Long: 39.03699 -99.03670

FR: 02/03/2004 Spd: 03/19/2004 Drig Cp: 03/26/2004 Issued: 07/19/2004 Revised: 09/17/2007

Copyright 2007 Independent Oil & Gas Service, Inc. Wichita, KS

Side 1

IP Status:

OIL, P 12 BO & 10 BWPD, SHAW 2722-2962 OA, LKC
3074-3202 OA, 4/22/2004

Revisions: INFO REL: 9/17/2007 - WAS OIL WELL -
TIGHT HOLE

Notes: CORR 2/4/2004 - ORIG FR 2280'FSL & 450'FEL

Contr: MURFIN DRILLING #16

Geol: RANDALL KILIAN

Elev: 1764 KB

Formation Tops: (L-Log, S-Sample, D-Driller)

L ANH	916 +848
L B/ANH	956 +808
S LANS D	2023 -259
L TOP	2692 -928
L HEEB	2940 -1176
L TOR	2958 -1194
L LANS A	2989 -1225
S LANS B	3002 -1238
S LANS C	3016 -1252

S LANS D	3034 -1270
S LANS E	3062 -1298
S LANS F	3074 -1310
S LANS G	3088 -1324
S LANS H	3124 -1360
S LANS I	3148 -1384
S LANS J	3166 -1402
S STARK	3190 -1426
S LANS K	3200 -1436
S HUSH	3214 -1450
S LANS L	3224 -1460
L BKC	3232 -1468
L CONG	3286 -1522
L ARB	3375 -1611
RTD	3454 -1690
LTD	3455 -1691

Csg: 8-5/8" 929 / 450 SX (ALT 1), 5-1/2" 3454 / 200 SX

Find:

COMMENT: WELL LOC BASED ON 3-D SEISMIC
INTRPRTN; MI & RURT 3/19/2004

Replacement Card

IA OPERATING
WICHITA KS 67212

6-12S-15W
2280'FSL & 450'FWL, SEC
KANSAS

#6-1 SUSAN

Copyright 2007 Independent Oil & Gas Service, Inc. Wichita, KS

Side 2

SHOWS: 2722-2732 (TOP LM, FR PORO,
STN-SATR, SFO, SLI ODOR), 2960-2968 (TOR LM,
PR-FR PORO, STN-SATR, SFO, SLI ODOR),
3292-3304 (CONG SD, QTZ, V FNE: GRN, WELL
SRTD CLEAN, SATR, SFO, NO ODOR)

NO CORES

DST(1) 2940-3012 (TOR, LANS A) 30-30-45-45,
(1ST OP) WK SURF BLO, ISI: NB, (2ND OP) NB,
FSI: NB, REC 3' M, W/OIL SPTS IN TOOO (SYS
CHL 6000 PPM) ISIP 151# FSIP 118# IFF 13#-21# /
FFP 23#-28# IHP 1436# FHP 1386# BHT 95°

DST(2) 3007-3110 30-30-45-45, (1ST OP) FB BLT
TO 5 INCH IN BKT, ISI: NB, (2ND OP) WB BLT TO
2 INCH IN BKT, FSI: NB, 60' GIP, REC 135' OCMW
(20% W, 10% OIL, 70% M) - (SMPL REC CHL
13,000 PPM, SYS CHL 6000 PPM) ISIP 412# FSIP
409# IFF 16#-70# / FFP 75#-87# IHP 1467# FHP
1425# BHT 97°

DST(3) 3142-3215 (LANS I-K) 30-30-60-60, (1ST
OP) WB BLT TO 1/2 INCH IN BKT, ISI: NB, (2ND
OP) WB BLT TO 1 INCH IN BKT, FSI: NB, 150' GIP,
REC 65' HOCM (10% G, 35% OIL, 65% M, SYS
CHL 6000 PPM) ISIP 122# FSIP 411# IFF 14#-33# /
FFP 36#-49# IHP 1557# FHP 1481# BHT 100°

Comp Info: TRGT ZN: LKC, ARB (OIL), PTD 3700

(ARB), MICT (3/26/2004) - CO, PF (LANS K)
3198-3202, W / 4 SPF, AC 250 GAL (15% MCA),
SWB LD, SO, RE-AC 750 GAL (15% MCA), SWB
LD, SO, PF (LANS J) 3167-3174, (LANS I) 3147-3151,
(LANS H) 3125-3128, W / 4 SPF, AC 750 GAL (15%
MCA), SWB LD, SO, RE-PF (LANS K) 3198-3202,
(LANS J) 3167-3174, (LANS I) 3147-3151, (LANS H)
3125-3128, W / 4 SPF, AC 2500 GAL (15% MCA),
SWB LD, RE-AC 250 GAL (15% MCA) & 750 GAL
(15% MA), SWB LD, SO, PF (LANS F) 3074-3078,
(TOR) 2959-2962, W / 4 SPF, AC 250 GAL (15%
MCA), SWB LD, SO, RE-AC 500 GAL (15% MCA),
SWB LD, SO, PF (TOP) 2722-2726, W / 4 SPF, AC
250 GAL (15% MCA), SWB LD, SO, RE-AC 500 GAL
(15% MCA), SWB LD, SO, SET 2-3/8" TBG AT 3220,
NO PKR, POP, IPP 12 BO & 10 BWPD (GR 34),
DOFP 4/22/2004, COMMINGLED