

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20296-00-00 \$ 188.⁵⁰
Spot: SWSESW Sec/Twnshp/Rge: 20-33S-32W
330 feet from S Section Line, 1625 feet from W Section Line
Lease Name: COLBURN Well #: 7-63
County: SEWARD Total Vertical Depth: 5800 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1639		WITH 900 SX CMT
PROD	4.5	5752	1720	WITH 450 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/24/2010 9:00 AM
Plug Co. License No.: 34391 Plug Co. Name: LASSO ENERGY SERVICES, LLC
Proposal Rcvd. from: MICHAEL POLLEY Company: HERMAN LOEB LLC Phone: (719) 342-5600

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/24/2010 2:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

PUMP 300# HULLS & 25 SX CMT @ 5684'. 1ST PLUG AT 1660' WITH 50 SX CMT. 2ND PLUG AT 500' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT. TOPPED OFF WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5691	5697		

6/04/10
2010061219

RECEIVED
JUN 03 2010
KCC WICHITA

Remarks: USED 60/40 POZMIX 5% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED
JUN - 1 2010
KCC DODGE CITY

Form 2/3