

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23102-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 6-9S-16W
4880 feet from S Section Line, 330 feet from W Section Line
Lease Name: KERN B Well #: 1
County: ROOKS Total Vertical Depth: 3425 feet

Operator License No.: 33759
Op Name: WINELAND OIL - LLC
Address: 304 N 3RD PO BOX 53
OTIS, KS 67565

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	208	0	w/140 sxs cmt
T1	2.875	3386		
PROD	5.5	3420	0	w/120 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/29/2010 8:00 AM
Plug Co. License No.: 32247 Plug Co. Name: CRAWFORD, JEFF DBA JEFF'S OILWELL SUPERVISION
Proposal Rcvd. from: JEFF CRAWFORD Company: WINELAND OIL - LLC Phone: (785) 387-2385

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 05/31/2010 5:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

05/29/2010
Had CIBP at 3000'.
Two days with pump and power swivel to drill out.
Got to 3250' and started binding. POOH.
05/31/2010
Ran tubing to 3250' - pumped 50 sxs neat 60/40 pozmix - 4% gel cement - followed with 150 sxs cement with 600# hulls.
Pulled tubing to 1271'. Circulated cement to surface with 150 sxs cement.
Tied onto backside and pumped 25 sxs cement.
Max. P.S.I 500#.
Tied onto casing and pumped 35 sxs cement.
Max. P.S.I. 600#.

Perfs:

Top	Bot	Thru	Comments
3342			
3316			
3295			
3288			
3270			
3224			
3212			
3202			
3165			
3150			
3114			
3088			
3037			

6/07/10
2010061227

Remarks: SWIFT SERVICES, INC.-TICKET #17865.

Plugged through: TBG

District: 04

Signed _____

Case Morris

(TECHNICIAN)

RECEIVED

JUN 07 2010

KCC WICHITA

Form CP-2/3

JUN 02 2010

