

15-051-22744-0000

FORM CP-2

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. E. L. Miller of Pioneer Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Cities Service Company

Complete Address: 800 Sutton Place Bldg., Wichita, Ks. 67202

Lease Name: Calahan "A" Well No. #A-36

Location: 1575' FSL & 330' FWL of SW Sec. 24 Twp. 11 Rge. 17 (E) (W)

County: Ellis Total Depth: 3668'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. E. L. Miller was instructed to plug the well as follows:

8 5/8"-814' s. p. cuc. w/500 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem w/heavy mud between all plugs.

1st plug @ 780' w/70 sacks cement

2nd plug @ 300' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulate 10 sacks of cement in rat hole.

Very truly yours,

12-21-81

[Signature]
Conservation Division Agent