



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date Oct 9, 19 58, authorized the following plugging operation:

Operator's Full Name: Phillips Pet. Co.

Complete Address: Bartlesville, Okla.

Lease Name: Dewey Well No. 1

Location: C SW SE Sec. 8 Twp. 12 Rge. 34 (E) (W)

County: Logan Total Depth: 5390

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: Dry Hole

Operator was instructed to plug well as follows:

Gun pits cir hole with heavy mud, set 20 sax cement at 2450' let set for six hours, heavy mud to 540' and set another 20 sax cement thru drill pipe heavy mud to 180' set cementing plug and 20 sax cement, heavy mud to 40' set cementing plug 1/2 sac hulls and 10 sax cement to bottom of cellar.

Very truly yours,

Gilbert P. Leiker

Signed: Gilbert P. Leiker
Conservation Division Agent

RECEIVED
OCT 15 1958

10-15-1958