

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colcrado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-109-20,545-00-00 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Olympic Petroleum Company OPERATOR'S LICENSE NO. 5248

ADDRESS 2121 S. Columbia Ave., Tulas, OK 74114 PHONE # (918) 747-8091

LEASE (FARM) Bob Clark WELL NO. #1 WELL LOCATION C SW NE COUNTY Logan

SEC. 26 TWP. 12S RGE. 33 (E) or (W) TOTAL DEPTH 4725' PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 305' CEMENTED WITH 60-40 posmix-200 sx SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 2590' w/25 sx; 2nd plug @ 1525' w/100 sx; 3rd plug @ 340' w/40 sx; 4th plug @ 40' w/10 sx w/wiper plug; Total 190 sx 60-40 posmix 1/4# floccel per sx.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? No
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 3:30 a.m. 12-20-92

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley PHONE # (913) 674-5768

ADDRESS 216 E. McFarland, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie RTD, Inc. LICENSE NO. 3068

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

RECEIVED
STATE CORPORATION COMMISSION
01-19-1993
JAN 19 1993
CONSERVATION DIVISION
WICHITA, KANSAS

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack R. Wharton
(Operator or Agent)

DATE: Jan 15, 1993