

AFFIDAVIT AND COMPLETION FORM

ACO-1


This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

OPERATOR Beren Corporation API NO. 15-109-20,196-00-00
 ADDRESS 970 Fourth Financial Center COUNTY Logan
Wichita, KS 67202
 FIELD ELAINE
 **CONTACT PERSON Evan Mayhew LEASE KUHLMAN FARMS
 PHONE (316) 265-3311

PURCHASER Central Crude Corporation WELL NO. 1
 ADDRESS 402 Commerce Plaza WELL LOCATION NE NE
Wichita, Kansas 67202 Ft. from _____ Line and

DRILLING CONTRACTOR Abercrombie Drilling, Inc. Ft. from _____ Line of
 ADDRESS 801 Union Center the SEC. 4 TWP. 12S RGE. 34W
Wichita, KS 67202

PLUGGING CONTRACTOR _____
 ADDRESS _____
 TOTAL DEPTH 4820' PBD 4745
 SPUD DATE 10/27/81 DATE COMPLETED 11/06/81
 ELEV: GR 3222DF KB 3227



WELL PLAT
 (_____) or (Full) Section - Please indicate.

KCC
 KGS

DRILLED WITH (~~_____~~) (ROTARY) (~~_____~~) TOOLS
 Report of all strings set — surface, intermediate, production, etc. (New) / (~~used~~) casing.

Purpose of string	Size hole-drilled	Size casing set (in C.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	20#	327'	60-40 posmix	250	3% c.c., 2% gel.
Production	7-7/8"	4 1/2"	10.5#	4819'	60-40 pozmix	250	2% gel, 10% salt

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			2	DPJS	4698-4710
Size	Setting depth	Pecker set at			
2-3/8"	4740	--			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated
1000 gallons 15% CRA	4698-4710

TEST DATE: 1/9/82 PRODUCTION 68 BOPD, no water
 Date of first production 1/5/82 Producing method (flowing, pumping, gas lift, etc.) _____
 A.P.I. Gravity NA till sales
 RATE OF PRODUCTION PER 24 HOURS
 Oil 69 bbls. Gas -0- MCF Water 0 % 0 bbls. Gas-oil ratio _____ CFPB
 Disposition of gas (vented, used on lease or sold) _____ Producing interval(s) Johnson

** The person who can be reached by phone regarding any questions concerning this information.
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

RECEIVED
 02-10-1982
 FEB 10 1982

CONSERVATION DIVISION

Name of lowest fresh water producing stratum UNKNOWN Depth _____
 Estimated height of cement behind pipe Cement did circulate to surface.

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand & Clay	0	120		
Sand & Shale	120	330		
Shale & Sand	330	2305		
Shale	2305	2687		
Anhydrite	2687	2712		
Shale	2712	3550		
Shale & Lime	3550	4105		
Lime	4105	4210		
Lime & Shale	4210	4350		
Shale & Lime	4350	4391		
Lime	4391	4540		
Lime & Shale	4540	4585		
Lime	4585	4675		
Lime & Shale	4675	4723		
Lime	4723	4820		
Rotary Total Depth		4820		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

A F F I D A V I T


STATE OF KANSAS, COUNTY OF SEDGWICK SS,

DON W. BEAUCHAMP OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS GEOLOGIST FOR BEREN CORPORATION OPERATOR OF THE KUHLMAN FARMS LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON SAID LEASE HAS BEEN COMPLETED AS OF THE 5th DAY OF JANUARY 19 82, AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) *Don W. Beauchamp*
 SUBSCRIBED AND SWORN TO BEFORE ME THIS 8th DAY OF FEBRUARY 19 82



Karen G. Berry
 NOTARY PUBLIC

MY COMMISSION EXPIRES: November 4, 1984