


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Logan County, Sec. 32 Twp. 12S Rge. 33W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
W/2 SW NE

Lease Owner Beren Corporation
Lease Name Lee Well No. 1
Office Address 970 Fourth Financial Center, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed June 30 19 79
Application for plugging filed (verbally) June 30 19 79
Application for plugging approved (verbally) June 30 19 79
Plugging commenced June 30 19 79
Plugging completed June 30 19 79
Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top Bottom Total Depth of Well 4750'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

T.D. 4750'
Set first plug at 1650' with 250 sacks
second plug at 240' with 20 sacks
third plug at 40' with 10 sacks
rathole with 5 sacks.
Cemented with 50/50 posmix, 6% gel.
Plug was down at 9:15 a.m., 6-30-79.

RECEIVED
STATE CORPORATION COMMISSION
JUL - 6 1979
07-06-1979
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jerry A. Langrehr, Executive Vice-President (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) _____
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of July, 19 79



Sherrie L. Brooks
Notary Public.

My commission expires 8-21-82

CONTRACTOR'S WELL LOG

OPERATOR: Beren Corporation
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Lee #1
 LOCATION: W/2 SW NE, Section 32-12S-33W
 Logan County, Kansas
 SPUD DATE: June 18, 1979
 COMPLETION DATE: June 30, 1979

0	258	Sand and shale
258	2219	Shale and sand
2219	2563	Lime and shale
2563	3051	Shale and lime
3051	4006	Lime and shale
4006	4050	Lime
4050	4111	Lime and shale
4111	4135	Lime
4135	4151	Lime and shale
4151	4750	Lime
	4750	Rotary Total Depth

Spud hole at 6:00 p.m., June 18, 1979. Drilled 258' of 12 1/4" hole. Ran 6 joints of used 8-5/8" - 24# casing. Set at 257' with 150 sacks of 60/40 posmix, 3% Ca.Cl. Cement did circulate. Plug was down at 11:45 p.m., June 18, 1979.

T.D. 4750'. Set 1st plug at 1650' with 250 sacks, 2nd plug at 240' with 20 sacks, 3rd plug at 40' with 10 sacks and 5 sacks in the rathole. Cemented with 50/50 posmix, 6% gel. Plug was down at 9:15 a.m., June 30, 1979.

SAMPLE TOPS:

Anhydrite 2581'
 B/Anhydrite 2607'

RECEIVED
 STATE CORPORATION COMMISSION

JUL - 6 1979

07-06-1979

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jerry A. Langrehr, Executive Vice-President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Lee #1, W/2 SW NE, Section 32-12S-33W, Logan County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jerry A. Langrehr
 Jerry A. Langrehr
 Executive Vice-President

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 5th day of July, 1979.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 8-21-82.