

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-109,20,442-00-00

LEASE NAME WasseMiller

WELL NUMBER 1

3300 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 35 TWP. 12 RGE. 33 (R) or (W)

COUNTY Logan

Date Well Completed 7-27-87

Plugging Commenced 7-27-87

Plugging Completed 7-27-87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Davis Petroleum, Inc.

ADDRESS Route 1 Box 183-B Great Bend, KS 67530

PHONE#(316) 793-3051 OPERATORS LICENSE NO. 4656

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dave Wann

to be filed by operator
 Is ACO-1 filed? operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4740'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Bottom Plug: @ 2600' w/25 sacks cement thru drill pipe
 Next Plug: @ 1535' w/100 sacks cement & 1 sack Flo Seal Thru Drill Pipe
 Next Plug: @ 430' w/40 sacks cement thru drill pipe
 Top Plug: @ 40' w/10 sacks cement
 (If additional description is necessary, use BACK OF THIS FORM.)

Name of Plugging Contractor Lobo Drilling Company License No. 5864

Address P.O. Box 877 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Ervin Neighbors

(Employee of Operator) or ~~XXXXXXXXXX~~ of

above-described well, being first duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors

(Address) P.O. Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 30 day of July, 1987

STATE OF Kansas Dorothy M. Hague
 Notary Public

DOROTHY M. HAGUE
 NOTARY PUBLIC
 STATE OF KANSAS
 My Appt. Exp. _____

Commission Expires: 5-5-90

07-31-1987
 WICHITA, KANSAS

15-109-20442-00-00

DRILLER'S WELL LOG

DATE COMMENCED: July 20, 1987
DATE COMPLETED: July 27, 1987

Davis Petroleum, Inc.
HASSEMILLER #1
C SW NW
Sec. 35, T12S, R33W
Logan County, Ks.

ELEVATION: 3009 K.B.

0 - 2587' Surface Soft, Clay, Shale
2587 - 2607' Anhydrite
2607 - 4021' Shale & Lime
4021 - 4025' Shale
4025 - 4064' Lime & shale
4064 - 4292' Lime
4292 - 4399' Shale & Lime
4399 - 4500' Lime, Shale, Chert
4500 - 4622' Lime
4622 - 4722' Shale
4722 - 4740' Chert & Lime
4740' RTD

FORMATION DATA

Anhydrite 2587'
Heebner 4021'
Lansing 4064'
Stark 4292'
Base K.C. 4399'
Marmaton 4500'
Pawnee 4557'
Ft. Scott 4622'
Johnson 4722'
Mississippi 4740'
RTD 4740'

Surface Pipe: Set new
8-5/8", 20# pipe 0307'
w/230 sacks 50/50 pozmix
2% gel 3% cc.

AFFIDAVIT

STATE OF KANSAS
COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors

Subscribed and sworn to before me this 30 day of July 1987.



Dorothy M. Hague
Notary Public

JUL 31 1987