

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-109-20,502-00-00

LEASE NAME Opal Hays

WELL NUMBER #1

1650' Ft. from S Section Line

990' Ft. from E Section Line

SEC. 31 TWP. 12S RGE. 33 (E) or (W)

COUNTY Logan

Date Well Completed _____

Plugging Commenced 4-13-91

Plugging Completed 4-14-91

LEASE OPERATOR Abercrombie Drilling, Inc.

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202

PHONE# (316) 262-1841 OPERATORS LICENSE NO. 5422

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-14-91 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation LKC-Marmaton Depth to Top _____ Bottom T.D. 4770'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	333'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Fill w/heavy mud; set 1st plug @ 2550'-2450' w/25 sx; 2nd plug @ 1535'-1135' w/100 sx;
3rd plug @ 385'-225' w/40 sx; 4th plug @ 40'-surface w/10 sx; rathole 15 sx; 60-40
posmix, 6% gel 1/4# Floseal.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Suite 801, Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801, Wichita, KS 67202



SUBSCRIBED AND SWORN TO before me this 13th day of May, 1991

Angela Woodard
Notary Public

My Commission Expires: 3-20-93

RECEIVED
STATE CORPORATION COMMISSION

MAY 15 1991
05-15-1991
CONSERVATION DIVISION
WICHITA, KANSAS