

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-109-20,478 -00-00

LEASE NAME Smith

WELL NUMBER 2-29

1320' Ft. from S Section Line

990' Ft. from E Section Line

SEC. 29 TWP. 12 SRGE. 33 ~~XXX~~ (W)

COUNTY Logan

Date Well Completed 8-2-89

Plugging Commenced 8-2-89

Plugging Completed 8-2-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Landmark Oil Exploration, Inc.

ADDRESS 250 N. Water - Suite 308, Wichita, KS 67202

PHONE# (316) 265-8181 OPERATORS LICENSE NO. 06113

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? YES

Which KCC Office did you notify? Dave Wann

Is ACO-1 filed? NO If not, is well log attached? NO

Producing Formation ACO-1 and well log will be filed by Operator.
N/A Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	279'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Spotted 25 sx. cement @ 2610' thru drill pipe.
Spotted 100 sx. cement @ 1570' thru drill pipe.
Spotted 40 sx. cement @ 325' thru drill pipe.
Spotted Plug & 10 sx. cement @ 40' thru drill pipe. Spotted 15 sx. cement in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420 RECEIVED
STATE CORPORATION COMMISSION

Address 401 E. Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

David F. Jamis, (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) David F. Jamis
(Address) 401 E. Douglas Suite 500
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 10th day of August, 19 89

Carolyn J. Tjaden
Notary Public

My Commission Expires _____
CAROLYN J. TJADEN
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. Sept. 5, 1992

RECEIVED
AUG 10 1989
06-10-1989
CONSERVATION DIVISION
Wichita, Kansas



ORIGINAL

15-109-20478-00-00

WHITE

AND ELLIS DRILLING, Inc.

RELEASED

AUG 9 1989

DRILLERS LOG

FROM CONFIDENTIAL

OPERATOR: Landmark Oil Exploration, Inc., 250 N. Water - Suite 308, Wichita, KS 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500, Wichita, Ks. 67202

Lease Name Smith Well No. 2-29

Sec. 29 T. 12S R. 33W Spot W/2 E/2 SE

County Logan State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 279' with 105 sx. standard and 70 sx. Posmix A 3% Gel
2% CC

Production: _____ @ _____ with _____ sx.


Type Well: D & A Total Depth 4750'

Drilling Commenced 7-25-89 Drilling Completed 8-2-89

Formation	From	To	Tops
Cellar	0	7	
Shale, Shells	7	2200	
Shale	2200	2630	
Sand, Shale	2630	3360	
Shale	3360	4750	

RECEIVED
STATE CORPORATION COMMISSION

AUG 25 1989
08-25-1989
CONSERVATION DIVISION
Wichita, Kansas



15-109-20478-00-00

WHITE

ANDELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Landmark Oil Exploration, Inc., 250 N. Water - Suite 308, Wichita, KS 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500, Wichita, Ks. 67202

Lease Name Smith Well No. 2-29

Sec. 29 T. 12S R. 33W Spot W/2 E/2 SE

County Logan State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 279' with 105 sx. standard and 70 sx. Posmix A 3% Gel 2% CC

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 4750'

Drilling Commenced 7-25-89 Drilling Completed 8-2-89

Formation	From	To	Tops
Cellar	0	7	
Shale, Shells	7	2200	
Shale	2200	2630	
Sand, Shale	2630	3360	
Shale	3360	4750	

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1989
08-10-1989
CONSERVATION DIVISION
Wichita, Kansas